

# UNITIZED GLASS CURTAIN WALL

KW SYNERGY  
since 1997

**\*FACTORY-PREFABRICATED unit for QUALITY CONTROL and FAST SITE INSTALLATION\***



Factory as at Work Site Materials

Insulated Glass Unit  
(Factory Glazed & Sealed)

Internal Permanent  
Air/Water Seal

Stack Joint Connection  
(Drainage Path)

EPDM Gaskets

Thermal Break  
(Optional)

Interlocking Profile  
(Aluminum Extrusions)

Panel Hanger Bracket  
(Factory Attached)



Fire and Safety  
Systems

Designed for **PRESSURE  
EQUALIZATION & RAIN  
SCREEN** principle:

- relieve dynamic wind pressure.
- drain infiltrated water.
- minimize air infiltration

## Fire & Safety System

- Insulated Glass Unit  
(Factory Glazed & Sealed)
- Internal Permanent  
Air/Water Seal
- EPDM Gaskets
- Thermal Break: (Optional)
- Interlocking Profile  
(Aluminum Extrusions)
- Panel Hanger Bracket  
(Factory Attached)

KW SYNERGY  
kysynergy.net